

CONTRACT SCHEDULE

Category 1: Quantities of Asbestos-Containing Materials are estimated. Samples will be taken and reports will be provided before a Notice to Proceed is issued on these items of work.

| Parcel 5, 1300 Jeffersonville Road, on Project No. 5240-06 | |
|---|------------------|
| (2-story, 3636-SF commercial building with 2 USTs on site) | |
| Estimated or Assumed (NTAs) Approximate Quantity | Total Task Price |
| Asbestos Abatement of 8,000 SF of SR/JC | |
| Asbestos Abatement of 300 LF of exterior caulk | |
| Asbestos Abatement of 80 SF of roof flashing tar | |
| Asbestos Abatement of 2,000 SF of floor tile/mastic | |
| Asbestos Abatement of 2 sinks undercoat | |
| Asbestos Abatement of 18 units/windows glaze | |
| Closure/Removal of (1) 750-gallon Underground Storage Tank, buried 6 feet deep | |
| Closure/Removal of (1) 1200-gallon Underground Storage Tank, buried 6 feet deep | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement, Demolition, and UST Removals: | |

| Parcel 32, 1542 Jeffersonville Road, on Project No. 5240-06 | |
|--|------------------|
| (One-story, 2783-SF residence and barn w/additional SF) | |
| Estimated or Assumed (NTAs) Approximate Quantity | Total Task Price |
| Asbestos Abatement of 4,000 SF of SR/JC | |
| Asbestos Abatement of 200 LF exterior caulk | |
| Asbestos Abatement of 10 LF roof flashing tar | |
| Asbestos Abatement of 500 SF floor tile/mastic on wood | |
| Asbestos Abatement of 500 SF vinyl flooring; | |
| Asbestos Abatement of 18 units/windows w/glaze | |
| Asbestos Abatement of 70 LF of white HVAC tape | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

CONTRACT SCHEDULE

| Parcel 6, 1762 Jeffersonville Road, on Project No. 5240-54A | |
|--|------------------|
| (One-story, 3960-SF restaurant) | |
| Estimated or Assumed (NTAs) Approximate Quantity | Total Task Price |
| Asbestos Abatement of 4,500 SF of SR/JC | |
| Asbestos Abatement of 40 LF interior caulk | |
| Asbestos Abatement of 100 SF roof flashing tar | |
| Asbestos Abatement of 1,520 SF floor tile-mastic | |
| Asbestos Abatement of 1,000 SF ACM siding | |
| Asbestos Abatement of 1,600 SF metal roof silver coat | |
| Asbestos Abatement of two asbestos concrete vents 30 SF | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

| Parcel 14, 1853 Jeffersonville Road, on Project No. 5240-54A | |
|--|------------------|
| (4817-SF auto-business building, including high-roof section, plaster, masonry, metal) | |
| Estimated or Assumed (NTAs) Approximate Quantity | Total Task Price |
| Asbestos Abatement of 300 SF of SR/JC | |
| Asbestos Abatement of 100 LF exterior caulk | |
| Asbestos Abatement of 55 SF roof flashing tar | |
| Asbestos Abatement of 2,900 SF floor tile | |
| Asbestos Abatement of 200 SF vinyl flooring | |
| Asbestos Abatement of two asbestos concrete vents 30 LF | |
| Asbestos Abatement of 6 units/window caulk/glaze | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

| Parcel 17A, 1895 Jeffersonville Road, on Project No. 5240-54A | |
|--|------------------|
| (One-story, 2365-SF commercial building, including flat roof, masonry) | |
| Estimated or Assumed (NTAs) Approximate Quantity | Total Task Price |
| Asbestos Abatement of 800 SF of SR/JC | |
| Asbestos Abatement of 160 LF exterior window-door caulk | |
| Asbestos Abatement of 2,200 SF silver coat multi-ply roofing | |
| Asbestos Abatement of 1,800 SF floor tile | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

CONTRACT SCHEDULE

| Parcel 21, 1935 Jeffersonville Road, on Project No. 5240-54A | |
|---|------------------|
| (One-story, 1908-SF residence) | |
| Estimated or Assumed (NTAs) Approximate Quantity | Total Task Price |
| Asbestos Abatement of 1,100 SF of SR/JC | |
| Asbestos Abatement of 100 LF interior caulk | |
| Asbestos Abatement of 1.900 SF roofing | |
| Asbestos Abatement of 600 SF floor tile; | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

Category 2: Asbestos Surveys have been completed, and reports are in appendix:

| Parcel 13, 1378 Jeffersonville Road, on Project No. 5240-06 | |
|--|------------------|
| (One-story, 1169-SF residence) | |
| Bid Item | Total Task Price |
| Asbestos Abatement (See Report in Appendix.) | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

| Parcel 15, 1394 Jeffersonville Road, on Project No. 5240-06 | |
|--|------------------|
| (One-story, 2335-SF residence and one-story brick outbuilding) | |
| Bid Item | Total Task Price |
| Asbestos Abatement of Main Building (See Report in Appendix.) | |
| Asbestos Abatement of Outbuilding (See Report in Appendix.) | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

| Parcel 21, 750 Sunnydale Drive, on Project No. 5240-06 | |
|---|------------------|
| (One-story, 1508-SF residence) | |
| Bid Item | Total Task Price |
| No Asbestos Abatement Expected (See Report in Appendix.) | \$0.00 |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

| Parcel 32A, 1548 Jeffersonville Road, on Project No. 5240-06 | |
|---|------------------|
| (One-story, 948-SF residence) | |
| Bid Item | Total Task Price |
| Asbestos Abatement (See Report in Appendix.) | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

CONTRACT SCHEDULE

| | |
|--|-------------------------|
| Parcel 37, 1632 Jeffersonville Road, on Project No. 5240-06 | |
| (One-story, 1224-SF residence) | |
| Bid Item | Total Task Price |
| Asbestos Abatement (See Report in Appendix.) | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

| | |
|--|-------------------------|
| Parcel 38, 1648 Jeffersonville Road, on Project No. 5240-06 | |
| (One-story, 1832-SF residence) | |
| Bid Item | Total Task Price |
| Asbestos Abatement (See Report in Appendix.) | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

| | |
|--|-------------------------|
| Parcel 45, 2220 Jeffersonville Road, on Project No. 5240-54A | |
| (One-story, 1025-SF commercial building, brick, former store - #2216 on building) | |
| Bid Item | Total Task Price |
| Demolition, including removal of all structures on parcel (No Asbestos--See Report in Appendix.) | |
| Total Price for Abatement and Demolition: | |

| | |
|---|-------------------------|
| Parcel 47, 2260 Jeffersonville Road, on Project No. 5240-54A | |
| (One-story, 1726-SF residence) | |
| Bid Item | Total Task Price |
| Asbestos Abatement (See Report in Appendix.) | |
| Demolition, including removal of all structures on parcel | |
| Total Price for Abatement and Demolition: | |

Category 3: Removal of miscellaneous items from required rights of way and easements on other parcels. (Photographs of items are in appendix.) Items that the property owners remove themselves at their discretion will be deleted from this contract.

Miscellaneous Items on Other Parcels on Project No. 5240-06

| Parcel | Description | Price to Remove Item(s) |
|--|--|-------------------------|
| 3 | 50 linear feet of landscaping timbers | |
| 6 | 3' x 12' brick wall, two 4' high brick columns topped with one 2' x 3' concrete lion and one 1' x 2' concrete ball | |
| 22-S-1 | 5' x 3' wooden double-faced sign | |
| 28 | 4' tall light pole | |
| 29 | concrete steps | |
| 30 | 5' x 5' concrete pad, possible septic tank lid | |
| 30 | removal or closure of septic tank, if present | |
| 36 | 250' chain-link fence, 3 concrete bollards | |
| 39-S-1 | 10' double-pole metal sign frame in driveway easement | |
| Total Price for Removing Misc. Items on Other Parcels on 5240-06: | | |

Miscellaneous Items on Other Parcels on Project No. 5240-54A

| Parcel | Description | Price to Remove Item(s) |
|--------|---|-------------------------|
| 5-S-1 | 6' x 8' wooden sign (A&M Metals) | |
| 8-S-1 | 15' tall vacant single-pole metal sign frame | |
| 9 | 3' tall steel I-beam; 1' tall steel sign post | |
| 9-S-1 | 7' x 10' two-sided concrete block frame sign (Bethel Church) | |
| 9A | four 3' tall steel I-beams | |
| 9A-S-1 | 3' x 4' rusted metal "Do Not Enter" sign | |
| 11 | concrete steps | |
| 12 | 2' tall x 200' long brick wall; 2' tall steel I-beam | |
| 12-S-1 | 4' x 8' two-sided plastic canvas sign on four posts | |
| 12-S-2 | 3' x 6' two-sided plastic canvas sign and one 6' tall steel pole | |
| 12-S-3 | 4' x 7' 1-sided lighted metal sign on two 6' tall metal poles | |
| 12-S-4 | 4' x 6' 1-sided wood sign on two posts | |
| 15 | 2' tall x 50' long brick wall | |
| 16-L-1 | 12' tall double light in a 3' x 10' concrete island with a water faucet and electrical outlet | |
| 16-L-2 | 20' tall strain pole with 1 light and a concrete base | |

CONTRACT SCHEDULE

| | | |
|--------|--|--|
| 16-L-3 | 12' tall double-light in 3' x 10' concrete island with a water faucet | |
| 17 | 150 linear feet of chain-link fence | |
| 18/20 | 100 linear feet of white 2-rail vinyl fence | |
| 18-S-1 | 4' x 6' wood sign on two posts (Sunoco Sign) | |
| 19 | air pump; 300 linear feet of curbing; 10' tall steel pole | |
| 19-S-1 | 18' tall two-sided digital sign (Jim Food Mart Sign) | |
| 26 | 60 linear feet of 8' tall security fence with 3 strands of barbed wire on top | |
| 26 | 4 large granite boulders | |
| 26-S-1 | 15' x 15' two-sided steel sign (Midstate steel Sign) | |
| 27-S-1 | 6' x 8' two-sided wood sign on two posts | |
| 28 | 2 conc. steps; 1' x 30' brick landscaping wall; 3' x 10' brick planter, conc. walk | |
| 28-S-1 | 20' x 10' two-sided lighted sign on two steel poles (True Faith Church Sign) | |
| 28-S-2 | 12' x 6' single-faced wood sign on two posts (Cross Keys Devine Restoration Sign) | |
| 30 | 1' x 20' concrete wall | |
| 30 | wire fence | |
| 31 | 150 liner feet of chain-link fence | |
| 32 | 75 linear feet of chain-link fence (mostly down) | |
| 36 | 50 linear feet of chain-link fence; 100 linear feet of concrete curbing | |
| 36 | 2 concrete steps, walk | |
| 36-S-1 | 7' x 4' two-sided vinyl sign (Divine Harmony Baptist Church Sign) | |
| 38 | 4' x 30' concrete wall | |
| 44 | 75' chain-link fence with wooden posts | |
| 46 | 300 linear feet of chain-link fence | |
| 47A | 8' x 60' security fence with 3 strands of barbed wire on top | |
| 47B | 100' chain-link fence | |
| 48 | 30 linear feet of chain-link fence | |
| 48-S-1 | 4' x 6' two-pole wooden sign, 5 large wood posts | |
| 48A | 30 linear feet of chain-link fence | |
| 49 | brick steps | |
| 50 | 100 linear feet of concrete curbing; 7 parking spaces in asphalt parking lot | |
| 51-S-1 | 15' tall two-sided lighted sign on two steel poles (car wash sign) | |
| 51-L-1 | 20' tall double security light | |
| 52 | concrete steps | |
| 54 | brick steps | |
| 55 | 100 linear feet of concrete curbing | |
| 55-S-1 | 4' x 8' two-sided wood sign on three posts (for sale sign) | |
| 55-S-2 | 3' x 5' two-sided wood sign (Newport Sign) | |

CONTRACT SCHEDULE

| | | |
|---|---|--|
| 55-S-3 | 12' steel pole sign holder (with temporary Maverick cigarettes sign and ATM sign) | |
| 58-S-1 | 5' x 8' plastic canvas sign on two posts | |
| 60 | block wall (in existing right of way) | |
| 63-S-1 | 15' tall 2-sided lighted sign on steel pole, conc. pedestal (Triangle Food & Gas) | |
| 63-L-1 | single security light on power pole | |
| 63-L-2 | single security light on power pole | |
| 70 | 175 linear feet of chain-link fence | |
| 71 | metal carport | |
| 73 | 100 linear feet of chain-link fence | |
| 74 | 100 linear feet of chain-link fence | |
| 75 | 110 linear feet of cement block and stucco wall with four lights | |
| 76 | 50 linear feet of concrete block and stucco wall; 75' x 6' wood privacy fence | |
| 78 | 90 linear feet of rusty metal ornamental fence (mostly down) | |
| 79 | 60 linear feet of chain-link fence | |
| 81 | satellite dish | |
| 83 | 15 linear feet of chain-link and metal privacy fence | |
| Total Price for Removing Misc. Items on Other Parcels on 5240-54A: | | |

| | |
|---|-------------------|
| Item No. 730-0000, Miscellaneous Construction | \$5,000.00 |
|---|-------------------|

Sum of Bid Prices: