

# CONTRACT SCHEDULE

**Category 1: Quantities of Asbestos-Containing Materials are estimated. Samples will be taken and reports will be provided before a Notice to Proceed is issued on these items of work.**

<b>Parcel 5, 1300 Jeffersonville Road, on Project No. 5240-06</b>	
(2-story, 3636-SF commercial building with 2 USTs on site)	
<b>Estimated or Assumed (NTAs) Approximate Quantity</b>	<b>Total Task Price</b>
Asbestos Abatement of 8,000 SF of SR/JC	
Asbestos Abatement of 300 LF of exterior caulk	
Asbestos Abatement of 80 SF of roof flashing tar	
Asbestos Abatement of 2,000 SF of floor tile/mastic	
Asbestos Abatement of 2 sinks undercoat	
Asbestos Abatement of 18 units/windows glaze	
Closure/Removal of (1) 750-gallon Underground Storage Tank, buried 6 feet deep	
Closure/Removal of (1) 1200-gallon Underground Storage Tank, buried 6 feet deep	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement, Demolition, and UST Removals:</b>	

<b>Parcel 32, 1542 Jeffersonville Road, on Project No. 5240-06</b>	
(One-story, 2783-SF residence and barn w/additional SF)	
<b>Estimated or Assumed (NTAs) Approximate Quantity</b>	<b>Total Task Price</b>
Asbestos Abatement of 4,000 SF of SR/JC	
Asbestos Abatement of 200 LF exterior caulk	
Asbestos Abatement of 10 LF roof flashing tar	
Asbestos Abatement of 500 SF floor tile/mastic on wood	
Asbestos Abatement of 500 SF vinyl flooring;	
Asbestos Abatement of 18 units/windows w/glaze	
Asbestos Abatement of 70 LF of white HVAC tape	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

# CONTRACT SCHEDULE

<b>Parcel 6, 1762 Jeffersonville Road, on Project No. 5240-54A</b>	
(One-story, 3960-SF restaurant)	
Estimated or Assumed (NTAs) Approximate Quantity	Total Task Price
Asbestos Abatement of 4,500 SF of SR/JC	
Asbestos Abatement of 40 LF interior caulk	
Asbestos Abatement of 100 SF roof flashing tar	
Asbestos Abatement of 1,520 SF floor tile-mastic	
Asbestos Abatement of 1,000 SF ACM siding	
Asbestos Abatement of 1,600 SF metal roof silver coat	
Asbestos Abatement of two asbestos concrete vents 30 SF	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 14, 1853 Jeffersonville Road, on Project No. 5240-54A</b>	
(4817-SF auto-business building, including high-roof section, plaster, masonry, metal)	
Estimated or Assumed (NTAs) Approximate Quantity	Total Task Price
Asbestos Abatement of 300 SF of SR/JC	
Asbestos Abatement of 100 LF exterior caulk	
Asbestos Abatement of 55 SF roof flashing tar	
Asbestos Abatement of 2,900 SF floor tile	
Asbestos Abatement of 200 SF vinyl flooring	
Asbestos Abatement of two asbestos concrete vents 30 LF	
Asbestos Abatement of 6 units/window caulk/glaze	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 17A, 1895 Jeffersonville Road, on Project No. 5240-54A</b>	
(One-story, 2365-SF commercial building, including flat roof, masonry)	
Estimated or Assumed (NTAs) Approximate Quantity	Total Task Price
Asbestos Abatement of 800 SF of SR/JC	
Asbestos Abatement of 160 LF exterior window-door caulk	
Asbestos Abatement of 2,200 SF silver coat multi-ply roofing	
Asbestos Abatement of 1,800 SF floor tile	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

# CONTRACT SCHEDULE

**Category 2: Asbestos Surveys have been completed, and reports are in appendix:**

<b>Parcel 13, 1378 Jeffersonville Road, on Project No. 5240-06</b>	
(One-story, 1169-SF residence)	
<b>Bid Item</b>	<b>Total Task Price</b>
Asbestos Abatement (See Report in Appendix.)	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 15, 1394 Jeffersonville Road, on Project No. 5240-06</b>	
(One-story, 2335-SF residence and one-story brick outbuilding)	
<b>Bid Item</b>	<b>Total Task Price</b>
Asbestos Abatement of Main Building (See Report in Appendix.)	
Asbestos Abatement of Outbuilding (See Report in Appendix.)	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 21, 750 Sunnydale Drive, on Project No. 5240-06</b>	
(One-story, 1508-SF residence)	
<b>Bid Item</b>	<b>Total Task Price</b>
No Asbestos Abatement Expected (See Report in Appendix.)	\$0.00
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 32A, 1548 Jeffersonville Road, on Project No. 5240-06</b>	
(One-story, 948-SF residence)	
<b>Bid Item</b>	<b>Total Task Price</b>
Asbestos Abatement (See Report in Appendix.)	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 37, 1632 Jeffersonville Road, on Project No. 5240-06</b>	
(One-story, 1224-SF residence)	
<b>Bid Item</b>	<b>Total Task Price</b>
Asbestos Abatement (See Report in Appendix.)	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

# CONTRACT SCHEDULE

<b>Parcel 38, 1648 Jeffersonville Road, on Project No. 5240-06</b> (One-story, 1832-SF residence)	
<b>Bid Item</b>	<b>Total Task Price</b>
Asbestos Abatement (See Report in Appendix.)	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 21, 1935 Jeffersonville Road, on Project No. 5240-54A</b> (One-story, 1908-SF residence)	
<b>Estimated or Assumed (NTAs) Approximate Quantity</b>	<b>Total Task Price</b>
Asbestos Abatement of 1,100 SF of SR/JC	
Asbestos Abatement of 100 LF interior caulk	
Asbestos Abatement of 1.900 SF roofing	
Asbestos Abatement of 600 SF floor tile;	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 45, 2220 Jeffersonville Road, on Project No. 5240-54A</b> (One-story, 1025-SF commercial building, brick, former store - #2216 on building)	
<b>Bid Item</b>	<b>Total Task Price</b>
Demolition, including removal of all structures on parcel (No Asbestos-- See Report in Appendix.)	
<b>Total Price for Abatement and Demolition:</b>	

<b>Parcel 47, 2260 Jeffersonville Road, on Project No. 5240-54A</b> (One-story, 1726-SF residence)	
<b>Bid Item</b>	<b>Total Task Price</b>
Asbestos Abatement (See Report in Appendix.)	
Demolition, including removal of all structures on parcel	
<b>Total Price for Abatement and Demolition:</b>	

# CONTRACT SCHEDULE

**Category 3: Removal of miscellaneous items from required rights of way and easements on other parcels. (Photographs of items are in appendix.) Items that the property owners remove themselves at their discretion will be deleted from this contract.**

### Miscellaneous Items on Other Parcels on Project No. 5240-06

Parcel	Description	Price to Remove Item(s)
3	50 linear feet of landscaping timbers	
6	3' x 12' brick wall, two 4' high brick columns topped with one 2' x 3' concrete lion and one 1' x 2' concrete ball	
22-S-1	5' x 3' wooden double-faced sign	
26	4' tall light pole	
29	concrete steps	
30	5' x 5' concrete pad, possible septic tank lid	
30	removal or closure of septic tank, if present	
36	250' chain-link fence, 3 concrete bollards	
39-S-1	10' double-pole metal sign frame in driveway easement	
<b>Total Price for Removing Misc. Items on Other Parcels on 5240-06:</b>		

### Miscellaneous Items on Other Parcels on Project No. 5240-54A

Parcel	Description	Price to Remove Item(s)
5-S-1	6' x 8' wooden sign (A&M Metals)	
8-S-1	15' tall vacant single-pole metal sign frame	
9	3' tall steel I-beam; 1' tall steel sign post	
9-S-1	7' x 10' two-sided concrete block frame sign (Bethel Church)	
9A	four 3' tall steel I-beams	
9A-S-1	3' x 4' rusted metal "Do Not Enter" sign	
11	concrete steps	
12	2' tall x 200' long brick wall; 2' tall steel I-beam	
12-S-1	4' x 8' two-sided plastic canvas sign on four posts	
12-S-2	3' x 6' two-sided plastic canvas sign and one 6' tall steel pole	
12-S-3	4' x 7' 1-sided lighted metal sign on two 6' tall metal poles	
12-S-4	4' x 6' 1-sided wood sign on two posts	
15	2' tall x 50' long brick wall	
16-L-1	12' tall double light in a 3' x 10' concrete island with a water faucet and electrical outlet	
16-L-2	20' tall strain pole with 1 light and a concrete base	
16-L-3	12' tall double-light in 3' x 10' concrete island with a water faucet	
17	150 linear feet of chain-link fence	
18/20	100 linear feet of white 2-rail vinyl fence	

# CONTRACT SCHEDULE

18-S-1	4' x 6' wood sign on two posts (Sunoco Sign)	
19	air pump; 300 linear feet of curbing; 10' tall steel pole	
19-S-1	18' tall two-sided digital sign (Jim Food Mart Sign)	
26	60 linear feet of 8' tall security fence with 3 strands of barbed wire on top	
26	4 large granite boulders	
26-S-1	15' x 15' two-sided steel sign (Midstate steel Sign)	
27-S-1	6' x 8' two-sided wood sign on two posts	
28	2 conc. steps; 1' x 30' brick landscaping wall; 3' x 10' brick planter, conc. walk	
28-S-1	20' x 10' two-sided lighted sign on two steel poles (True Faith Church Sign)	
28-S-2	12' x 6' single-faced wood sign on two posts (Cross Keys Devine Restoration Sign)	
30	1' x 20' concrete wall	
30	wire fence	
31	150 linear feet of chain-link fence	
32	75 linear feet of chain-link fence (mostly down)	
36	50 linear feet of chain-link fence; 100 linear feet of concrete curbing	
36	2 concrete steps, walk	
36-S-1	7' x 4' two-sided vinyl sign (Divine Harmony Baptist Church Sign)	
38	4' x 30' concrete wall	
44	75' chain-link fence with wooden posts	
46	300 linear feet of chain-link fence	
47A	8' x 60' security fence with 3 strands of barbed wire on top	
47B	100' chain-link fence	
48	30 linear feet of chain-link fence	
48-S-1	4' x 6' two-pole wooden sign, 5 large wood posts	
48A	30 linear feet of chain-link fence	
49	brick steps	
50	100 linear feet of concrete curbing; 7 parking spaces in asphalt parking lot	
51-S-1	15' tall two-sided lighted sign on two steel poles (car wash sign)	
51-L-1	20' tall double security light	
52	concrete steps	
54	brick steps	
55	100 linear feet of concrete curbing	
55-S-1	4' x 8' two-sided wood sign on three posts (for sale sign)	
55-S-2	3' x 5' two-sided wood sign (Newport Sign)	
55-S-3	12' steel pole sign holder (with temporary Maverick cigarettes sign and ATM sign)	
58-S-1	5' x 8' plastic canvas sign on two posts	
60	block wall (in existing right of way)	
63-S-1	15' tall 2-sided lighted sign on steel pole, conc. pedestal (Triangle Food & Gas)	

# CONTRACT SCHEDULE

63-L-1	single security light on power pole	
63-L-2	single security light on power pole	
70	175 linear feet of chain-link fence	
71	metal carport	
73	100 linear feet of chain-link fence	
74	100 linear feet of chain-link fence	
75	110 linear feet of cement block and stucco wall with four lights	
76	50 linear feet of concrete block and stucco wall, 7' x 6' wood privacy fence	
78	90 linear feet of rusty metal ornamental fence (mostly down)	
79	60 linear feet of chain-link fence	
81	satellite dish	
83	15 linear feet of chain-link and metal privacy fence	
<b>Total Price for Removing Misc. Items on Other Parcels on 5240-54A:</b>		

Item No. 730-0000, Miscellaneous Construction	\$5,000.00
---	------------

Sum of Bid Prices: