

01005 - STATEMENT OF WORK FOR TOBESOFKEE PERMANENT CABLE INSTALLATION

PART 1 - GENERAL

1.01 STATEMENT OF WORK: This is a general overview of the project. Follow details shown by the specifications and drawings, interpreted in accordance with contract clauses.

The flat cables on the east and west gate of Fenley Ryther Dam at Lake Tobesofkee have broken. All four cables shall be replaced. Provide all labor, material, plant, equipment, supplies, and coordination required to remove the existing cables and sockets. The contractors will bid to install new flat cables and sockets and remove the temporary wire rope slings in place on the east gate, place them in shipping containers for storage, and deliver to Tobesofkee Recreation Area or Public Works. Coordinate with the Project Manager to verify location.

The new cables and sockets have been requisitioned from Yarborough Cable Services, A Certex Company, Memphis, TN, Office: (901) 353-5383, Brad Herring, Yarborough Southeast Regional Manager, Cell: (901) 530-6440, bherring@certex.com. Availability is estimated at 28 weeks from April 18, 2024.

Contractor will coordinate delivery of cables with Yarborough Cable Services (see above).

Temporary Cables

Temporary cables were placed on the east gate in February 2024 to provide lifting capability during flat cable manufacturing period. Once the flat cables are installed, the temporary cables shall be placed into shipping containers and turned into the Tobesofkee Recreation Area on Moseley Dixon Road. Coordinate with the Project Manager to verify location.

B. The project is located at Fenley Ryther Dam, Lake Tobesofkee.

C. Price shall include all work needed to remove existing cables, including temporary cables and install new flat cables on both gates.

1.02 CONTRACT SITE AND WORK RESTRICTIONS:

A. Work area is restricted to the area at the construction site. The lake level restrictions provide only limited opportunity to close the east gate while working on the west gate. The ability to close the gate will depend on the level of inflow from upstream of the dam. The normal lake level is 360.0. The gate can be closed to allow the lake level to rise to 360.5. The length of time the lake will take after closure to rise to this level will depend on upstream flow conditions.

1.03 HOURS OF WORK:

A. Standard work hours for this project are normal work hours of 8:00 AM to 5:00 PM local time, Monday through Friday. Work must stop on official County holidays unless specifically approved in advance.

B. Alternate Work Hours

1. If the Contractor desires to work another set of standard hours submit written request five (5) workdays before the date desired to work the different standard.

01005 - STATEMENT OF WORK FOR TOBESOFKEE PERMANENT CABLE INSTALLATION

C. All references to days mean calendar days unless otherwise noted.

PART 2 - EXECUTION

3.01 COORDINATION: OMITTED

3.02 GOVERNMENT-FURNISHED PROPERTY

A. Pick items up from (where directed/shown). Coordinate this with the Engineer.

B. Materials remain Government property. The contractor is responsible for them from pickup to final acceptance.

C. This property and approximate amounts are as follows:

ITEM

Cable Pins and Washers for Permanent cables on the east gate.